

**Addendum #2**  
**IFB05102018**  
**Construction Services to Build Baseball Press Box**  
**McHenry County College**

This Addendum is in response to the inquiries from potential bidders. This Addendum constitutes changes to the specifications as sent out in the original IFB and other pertinent information shared with all vendors. All changes and information listed on this Addendum should be considered as the official modifications to the specifications and should be included in your proposal with these in mind.

Please acknowledge your receipt of this addendum by attaching a signed copy of the addendum with your proposal response.

Received and acknowledged by: \_\_\_\_\_

---

1. Owner performing all electric and painting work? None is shown to be done.  
**There is no electric noted on the plans so do not include any electrical work**
2. Prime finish on all siding and pieces?  
**All siding and trim to be prefinished. Installers will caulk all gaps and penetrations as needed and touch up any cut ends. No other painting would be needed.**
3. There are two berms on each side of the press box that will need to be cut into in order to install the foundation and slab. Please supply a grading plan. This will help quantify materials needed to be trucked in, how much excavation/grading/seeding work needs to be performed.  
**An engineering plan will be created. A visual inspection of the site and knowing the size of the structure will provide the information needed to understand how much material will need to be displaced and most likely removed. Top of Slab will be 6" above existing grade behind home plate.**